

TRIECA | 2019 CONFERENCE

Thank you to our sponsors:

www.trieca.com

GOLD SPONSORS

AECOM



AQUATECH



terrafix
geosynthetics inc.

UNILOCK
DESIGNED TO CONNECT.

GEMS
Disinfectant Environmental Management Services

Hydro International

R&M
CONSTRUCTION

filtrex
CANADA
LAND IMPROVEMENT SYSTEMS
let nature do it.



York Region

MEDIA SPONSORS

Environmental Science & Engineering
MAGAZINE

WATER
CANADA

PRINT SPONSOR

WARREN'S
WATERLESS PRINTING INC.

HOSTS

CAN+IECA
CANADIAN INSTITUTE OF ENVIRONMENTAL ENGINEERS

Toronto and Region Conservation Authority

From Design to Construction: Lessons Learned from Contractor Inexperience During Implementation of Erosion Mitigation at the Oshawa Landfill

Robin McKillop, M.Sc., P.Geo.
TRIECA conference
March 20, 2019



PALMER
ENVIRONMENTAL
CONSULTING
GROUP INC.



Contractor made up for inexperience in the implementation of naturalized in-stream/riparian works with an openness to direction, adjustment and field-fit refinements





Outline

- Project Overview
- Low Bid Implications
- Site Inspection Allowance
- Project Team Communication






PROJECT OVERVIEW





Oshawa Landfill

- Operational from 1960s until 1979
- Located in former sand/gravel pit
- Capped in 1980; now just site of transfer station





Oshawa Landfill



Erosion!



- Surface runoff (gullying)
- Fluvial scour
- Slope instability



PALMER
ENVIRONMENTAL
CONSULTING
GROUP INC.



Erosion assessment, design & permitting



1. Erosion inventory

– 18 erosion sites

2. Erosion risk evaluation

– 5 prioritized for mitigation

3. Erosion mitigation design


– 5 conceptual designs → 3 detailed designs

4. Erosion mitigation permitting

– CLOCA, DFO (LoA), MNRF



Oshawa Landfill





5. Tendering

- Region tendered implementation of Sites 1, 10 and 11, with support from Palmer/Greck team
- **Lowest bid tendering process!**
 - Original lowest bid disqualified (reference checks)
 - Next lowest bid awarded contract





6. Construction

- Erosion mitigation implemented successfully at all three sites in July-August 2018
- Region assumed Contract Admin role
 - ~Daily site inspections
- Palmer/Greck design team conducted limited site inspections
 - 3-5 per site, at strategic times



Site 1

Embedded woody debris

Riparian shrub plantings along regraded slope toe

Pool

Benched inner bank (improved floodplain accessibility)

Cobble riffle

Pool



Site 10

Salmon in lee of
woody debris
structure



Site 11

Living cedars
retained in slope-
toe protection



Embedded woody
debris





LOW BID IMPLICATIONS





Risks of accepting low bids

- Region's obligation to award construction to lowest (qualified) bid risks compromising quality and efficiency
 - More guidance required to compensate for inexperience in bioengineering along streams
 - Less precise implementation (equipment, method, sequence)
 - Slower (suboptimal coordination, need for revisions)





Erosion & sediment control issues

- **Coffer dams**
 - Poor seal & outflanking
 - Few ideas to improve
- **Sediment control**
 - Silt fence across channel
- **Dam-and-pump**
 - Incomplete isolation of work area; no sump
 - Clean upstream water discharged downstream into filter bag in channel
- **Fuel tank storage**
 - <5 m from creek, without spill protection





Design implementation issues

- Riparian plantings installed on wrong (inner) bank
- Native clay/silt fill placed along toe of bank at downstream tie-in
 - Shared responsibility – e.g. too few XSs





SITE INSPECTION ALLOWANCE






Frequency & duration of site inspections

- Time allocated to inspections by design team should be commensurate with contractor (in)experience
 - Also consider Contract Admin expertise
- Insufficient time available in budget to provide contractor guidance required (*as reaffirmed by him!*)
 - Questions arise, but no real-time, onsite feedback
 - Phone, text and email risk miscommunication or work delays





Cost-benefit analysis







PROJECT TEAM COMMUNICATION




Lines of communication





Avoiding miscommunication


- Site inspection logs
 - Initially sent to Region (approver); didn't always reach contractor promptly
 - Later distributed among entire project team in order to avoid delay/miscommunication
- Lag in responses to identified issues (e.g. silt fence maintenance) resolved
- Prompt, informal email communication better than formal logs?





Key takeaways

- Avoid low-bid tenders, where possible, or at least scrutinize experience and references and ensure designs are sufficiently detailed
- Allow for adequate site inspections by design team for ultimate cost savings
- Communicate issues promptly and broadly with entire project team
- Establish an open, collaborative working relationship with contractor to optimize design implementation





Questions?

robin@pecg.ca



PALMER
ENVIRONMENTAL
CONSULTING
GROUP INC.



TRIECA | 2019 CONFERENCE

Thank you to our sponsors:

www.trieca.com

GOLD SPONSORS

AECOM



AQUATECH



MEDIA SPONSORS



PRINT SPONSOR



HOSTS

