



SOURCE
2STREAM

2023
Conference

Canada's Premier
Stormwater and Erosion
and Sediment Control
Conference

Thank you to our sponsors!

EXECUTIVE SPONSORS



Canadian Society for
Civil Engineering



Société canadienne
de génie civil



OPPORTUNITIES SPONSOR

AECOM

MEDIA SPONSORS



HOSTS



Presented by:



In association with:



Farewell Creek Design-Build: Lessons Learned



Presenters:

Brad Fairley, BSc, MES

5 Smooth Stones Restoration Inc.

Ed Gazendam, PhD, PEng

Water's Edge Environmental Solutions Team Ltd.



Fairley

- Background
- Lessons Learned by Owner

Gazendam

- Lessons Learned by Designer
- Lessons Learned by Contractor

DBB vs DB

- Majority of stream restoration projects in Canada are delivered using a Design-Bid-Build Process
- Few stream restoration projects delivered using Design-Build (e.g., I am aware of 3)
- Usually as part of a larger project (e.g., road, bridge) that is being delivered using DB
- Mixed results
- More commonly used in the US by State In-lieu Fee Programs (Full Delivery Projects)
- US has proved that DB can be an efficient method for delivering stream projects



City of Oshawa

- Completed several stream restoration projects
- All done using DBB
- Problems with contractors
- Many had gone badly
- Lots of change orders
- Projects failing
- LOC tied up until projects fixed
- Farewell Creek
- Wanted to explore DB approach




5 | SMOOTH STONES
RESTORATION INC.

Farewell Creek (Palmer)

- Channel migrating
 - Steep eroding embankments upstream and downstream
 - Sediment loadings
- Gabion wall failing
 - Risk to fish passage (trout stream)
 - Threat to private property





Berm

Bank erosion
behind outflanked
boulder riprap

Low terrace

Flow

Vegetated
point bar

Scour pool
in till

Cobble riffle

4m-high
cut-bank

Gabion retaining wall

Terrace

1206

Carport

1210

TONES
INC.







Farewell Creek (Palmer)

- Palmer Options for Restoration
 1. Do Nothing
 2. Wall replacement
 3. Vegetated boulder revetment
 4. Meander realignment
- City Option (wanted a more permanent solution)
 5. Creek realignment



5 | SMOOTH STONES
RESTORATION INC.

DB Project Delivery

- Decided to retain a firm to guide them through the DB Process
- Hired 5SSR to work with the City:
 - Develop a Multi-Criteria Decision Matrix to select the preferred option for Farewell Creek
 - Write the RFP
 - Evaluate the proposals
 - Conduct a pre-bid meeting
 - Provide support during construction



5 | SMOOTH STONES
RESTORATION INC.

Owner Lesson 1: RFP

- 5SSR wrote the RFP and provided it to City for them to add boiler plate
- Both included a request for references but they requested different information
- Some DB Teams failed to respond to both requests
- The requests should have been rationalized



5 | SMOOTH STONES
RESTORATION INC.

Owner Lesson 2: LOC required by DFO

- City wanted to transfer risk to contractor
- Expected contractors to provide LOC
- 5SSR did some homework and concluded that the contractors would not respond to the RFP if LOC was a requirement
- Contractors had never dealt with DFO and assumed it was risky
- Not worried about project failing just thought DFO might not give them their money back
- Unfortunate because cost of money was very low in 2022



5 | SMOOTH STONES
RESTORATION INC.

Owner Lesson 3: Pre-bid Meeting

- 5SSR recommended an on-site pre-bid to make sure the DB Teams knew what was expected
- City cancelled because of Covid
- Distributed RFP
- 5SSR and the City thought that the RFP was clear that the City wanted the stream significantly realigned
- Only 1 DB Team submitted a proposal to do a significant realignment
- Apples and Oranges
- Left with only 1 responsive bidder



5 | SMOOTH STONES
RESTORATION INC.

Owner Lesson 4: Milestone Payments

- Contract specified that the City would pay 20% of total project budget over 3 years of post-construction monitoring (i.e., 5%, 5%, 10%)
- Did this in order to maintain leverage with contractor
- Learned contractors do not want to wait to be paid
- Inflated price of the project
- With only 1 responsive bidder, the City paid too much for the project



5 | SMOOTH STONES
RESTORATION INC.

Owner Lesson 5: Owner Involvement

- City was intimately involved in project and had a consultant assist them:
 - DB Team selection
 - Contract administration
 - Construction administration
- City failed to reap some of the benefits of DB project delivery (streamlining)



5 | SMOOTH STONES
RESTORATION INC.

Designer Lesson 6: Pay Attention and Build on That

- City issued RFP for channel realignment and slope stabilization
- Previous reports had identified a possible realignment
- We noticed existing bankfull bench in the field and used that to place the actual alignment
- City had identified vegetation removal and re-use so we included a lot of woody debris in the design
- Also identified a by-pass channel location that effectively allowed for the construction of the entire channel off-line



Designer Lesson 7: Trusting the Contractor

- DB team includes the designer and the contractor
- Implies that the team has great chemistry
- Also implies that the team trusts each other
- However, reality is that each member has a skill set and knows their respective area
- Designer still needs to have oversight which includes regular inspections
- But Contractor does have a great deal of independence in the construction process
- Designer has to build the relationship to create necessary trust



Designer Lesson 8: E&S Still Needs to be Inspected

- DB team prepared and implemented an effective Erosion & Sediment Control Plan
- DB Team still needs to inspect the controls regularly
- Everyone does what they do best and focus can deviate from the mundane
- While the contractor is on site, designer still needed to be on site to inspect



Contractor Lesson 9:

- Design intent was to have **Live Branches** incorporated in the stone
- During the install of the live branches and stone, it is imperative to install a large amount of branches
- During the install of stone and future flows, a lot of the live branches will be broken, lost/dried up and can look very sparse.



Contractor Lesson 10:

- **Woody Toe Debris** was part of the design
- When installing the logs in the woody debris toe bank protection, its always important to make sure logs are locked in/lodged into the soil
- Therefore, it is important to keep logs as long as possible when cutting
- After the install, some longer logs may pose a risk to collect debris, and so some logs were cut shorter.



Contractor Lesson 11:

- **Bypass Channel** was key component of the construction process
- Effectively by-passed flow to enable offline construction of the channel
- However, during a large storm event, an area of the plastic was damaged and caused a small washout of existing clay
- Using a thicker plastic or doubling up on the liner would be good practice in areas of high flows



Summary:

- DB is relatively new to stream restoration in Canada
- Lost of Lessons:
 - Owner
 - Designer
 - Contractor
- DB is coming to stream restoration, so get ready
- Despite all of the learning, the City got a great project!



Project excellence due to input from:



Questions?

Brad Fairley, MES
Director

5 Smooth Stones Restoration Inc.
Email: brad.fairley@fivessr.com
Tel.: (519) 591-4200

Ed Gazendam, Ph.D., P.Eng.
President

Water's Edge Environmental Solutions Team Ltd.
Email: ed@watersedge-est.ca
Tel.: (519) 651-2390



**SOURCE
2STREAM**

2023
Conference

Canada's Premier
Stormwater and Erosion
and Sediment Control
Conference

Thank you to our sponsors!

EXECUTIVE SPONSORS



Canadian Society for
Civil Engineering



Société canadienne
de génie civil



OPPORTUNITIES SPONSOR



MEDIA SPONSORS



HOSTS

Presented by:



In association with:

